

ADVERTISEMENT FOR BIDS

Village of Rosebush

3901 North Mission Rd

Rosebush, MI 48878

Separate sealed Bids for the construction of Rosebush drainage and street improvements will be received by Village of Rosebush at 3901 North Mission Rd, Rosebush, MI 48878 until 10:00 AM Local Time, May 12, 2010 and then at said location publicly opened and read aloud.

The Work includes the following major items:

- **1.15 miles of reconstruction, realigning and widening of Village streets with HMA pavement, curb and gutter, and intersection construction.**
- **Installation of storm sewer and adjustments to existing storm sewer and sanitary manholes.**
- **Installation of signs and pavement markings.**
- **Slope restoration.**

The Contract Documents, consisting of Advertisement for Bids, Information for Bidders, Bid, Bidder's Experience Form, Bid Bond, Agreement, Standard General Conditions of the Construction Contract, Supplemental General Conditions, Payment Bond, Performance Bond, Notice of Intent to Award, Notice to Proceed, Change Order, Maintenance Bond, Drawings, Specifications and Addenda, may be examined at the following locations:

Gourdie-Fraser, 123 West Front Street, Traverse City MI 49684

Copies of the Contract Documents may be obtained after April 24, 2010 from the office of Gourdie-Fraser, located at 123 West Front Street, Traverse City, Michigan 49684.

Payment Schedule - Make checks payable to Gourdie-Fraser

Plans and Specifications – Paper copy                      \$ 50.00                      (Non-Refundable)

Plans and Specifications – C.D. version                      \$ 25.00                      (Non-Refundable)

Payment must be received prior to release of Plans and Specifications. Make checks payable to Gourdie-Fraser. Faxed checks will not be accepted. We accept Visa, MasterCard, and Discover.

If shipping plans to Contractors through overnight mail an additional fee of \$20.00 will be charged.

For a list of planholders, please visit the Gourdie-Fraser website at [www.gourdiefraser.com](http://www.gourdiefraser.com), go into the Project Center, then Planholders Lists, then select the appropriate Project.

Engineer's Estimate is \$475,000.00.

Bidders are responsible to research Addendums and Acknowledge Addendums on the Bid form. Addendums will be posted, at least three (3) days prior to Bid Opening, on the Gourdie-Fraser website at [www.gourdiefraser.com](http://www.gourdiefraser.com), go into the Project Center, then Advertisements, then select the appropriate Project, Addendums will be at the end of the Advertisement for Bids.

Each Bidder must deposit with their Bid security in the amount and form as specified by the conditions provided in the Information for Bidders. Bids not accompanied by a proper Bid bond or certified check in the amount stated in the documents, or received after the above date and time will not be considered. Fax transmittals of Bids or Bid bonds will not be accepted.

The Owner reserves the right to waive any informalities or to reject any or all Bids.

This project requires Davis-Bacon Wage rates per the funding agreement between the Village and the state of Michigan. Current wage rates and effective dates are in the specification book for this project.

No Bidder may withdraw their Bid within 90 days after the actual date of Bid opening.

\_\_\_\_\_  
Advertisement Date

GOURDIE-FRASER  
123 West Front Street  
Traverse City, Michigan 49684

Date: April 30, 2010

**ADDENDUM #1**

<u>PROJECT</u>	<u>BIDS DUE</u>
Rosebush Drainage & Street Improvements GFA Project No: 09407	Date: May 12, 2010 Time: 10:00 am Location: Village of Rosebush 3901 North Mission Rd, Rosebush, MI 48878

This Addendum No. 1 is issued prior to the receipt of bid proposals to amend the Contract Documents and becomes part of the Contract Documents as of this date.

00400 BID FORM - USE THE ATTACHED BID FORM WHEN SUBMITTING YOUR  
BID.

This Addendum No. 1 supersedes the information in the originally issued Contract Documents where applicable. The Contractor shall acknowledge receipt of any Addendums on the Bid Form included with his/her bid.

**BID**

Proposal of \_\_\_\_\_  
(Hereinafter called "Bidder"), organized and existing under the Laws of the State of \_\_\_\_\_,  
doing business as \_\_\_\_\_,\* to \_\_\_\_\_

In compliance with your Request for Bids, Bidder hereby proposes to perform Work for the construction of Rosebush drainage and street improvements in strict accordance with the Contract Documents within the time set forth therein and at the prices stated below.

By submission of this Bid, each Bidder certifies, and in the case of a joint Bid, each party thereto certifies as to his own organization that this Bid has been arrived at independently, without consultation, communication, or agreement as to any matter relating to this Bid with any other Bidder or with any competitor.

Bidder hereby agrees to commence Work under this Contract on or before a date to be specified in the Notice to Proceed and to substantially complete the Project within 120 consecutive calendar days thereafter, and fully complete Project (including restoration, punch list items, maintenance bond, and close-out documents) within 60 days of Substantial Completion. Bidder further agrees to pay as liquidated damages, the sum of \$500.00 for each consecutive calendar day thereafter as provided in Section 00800 of the Supplemental General Conditions.

The Bidder hereby agrees to pay the actual cost for any construction observation, inspection, testing and project management time and expense for Engineering Services for work beyond the 60 work days. Bidder hereby agrees to also pay for the actual costs to the Owner for Resident Project Representative and Project management services and all additional inspection costs beyond the Contract completion date established by the "Notice to Proceed". (Reference – Section 00800 of the Supplemental Conditions.)

Bidder acknowledges receipt of the following Addendum:

\_\_\_\_\_  
\_\_\_\_\_

\*Insert "a Corporation", "a Partnership", or "an Individual" as applicable.

Bidder agrees to perform all work in the Contract Documents for the following prices:

	Pay Item	Description	Est. Quantity	Unit	Unit Price	Item Cost
1	1000001	Mobilization, Max. \$25,000	1	LS		
2	2020002	Tree, Rem, 19 inch to 36 inch	2	EA		
3	2020004	Tree, Rem, 6 inch to 18 inch	18	EA		
4	2030001	Culv, Rem, Less than 24 inch	23	EA		
5	2030011	Dr Structure, Rem	3	EA		
6	2030015	Sewer, Rem, Less than 24 inch	353	FT		
7	2040006	Curb and Gutter, Rem	173	FT		
8	2040011	Pavt, Rem	990	SYD		
9	2040013	Sidewalk, Rem	83	SYD		
10	2040030	Utility Pole, Rem	9	EA		
11	2050031	Roadway Grading	63	STA		
12	2050041	Subgrade Undercutting, Type II	1,200	CYD		
13	2080005	Erosion Control, Inlet Protection, Sediment Trap	45	EA		
14	2080025	Erosion Control, Silt Fence	1,000	FT		
15	2090001	Project Cleanup	1	LS		
16	3020001	Aggregate Base	5,500	TON		
17	3060015	Maintenance Gravel, LM	500	CYD		
18	3070025	Approach, CI II, 3 inch	1,611	SYD		
19	3070125	Shoulder, CI II, 3 inch	950	SYD		
20	4010860	Culv End Sect, Metal, 12 inch	47	EA		
21	4017001	Culv, CI A, 8 inch	835	FT		
22	4020005	Sewer, CI A, 15 inch, Tr Det A	310	FT		
23	4020033	Sewer, CI A, 12 inch, Tr Det B	1460	FT		
24	4030005	Dr Structure, 48 inch dia	20	EA		
25	4030051	Dr Structure Cover	18,135	LB		
26	4030052	Dr Structure Cover, Adj, Case 1	8	EA		
27	4030053	Dr Structure Cover, Adj, Case 2	17	EA		
28	4030064	Dr Structure, Tap, 12 inch	3	EA		
29	5020034	HMA, 13A T	1,900	TON		
30	5020034	HMA, 13A L	850	TON		
31	5020125	HMA, 13A, 2 inch	150	SYD		
32	8010005	Driveway, Nonreinf Conc, 6 inch	100	SYD		
33	8020016	Curb and Gutter, Conc, Det B2	1,578	FT		

	Pay Item	Description	Est. Quantity	Unit	Unit Price	Item Cost
34	8030002	Sidewalk, Conc, 4 inch	1,300	SFT		
35	8030011	Sidewalk Ramp, ADA	600	SFT		
36	8100197	Sign, Type III, Erect, Salv	6	EA		
37	8120001	Barricade, Type III, High Intensity, Furn	2	EA		
38	8120002	Barricade, Type III, High Intensity, Oper	2	EA		
39	8120030	Flag Control	1	LS		
40	8120040	Lighted Arrow, Type B, Furn	2	EA		
41	8120041	Lighted Arrow, Type B, Oper	2	EA		
42	8120050	Minor Traf Devices	1	LS		
43	8120100	Plastic Drum, High Intensity, Furn	50	EA		
44	8120101	Plastic Drum, High Intensity, Oper	50	EA		
45	8120120	Sign, Type B, Temp, Furn	150	SFT		
46	8120121	Sign, Type B, Temp, Oper	150	SFT		
47	8130010	Riprap, Plain	50	SYD		
48	8140010	Paved Ditch, HMA	120	SYD		
49	8160051	Slope Restoration, Type A	4,000	SYD		
50	8160052	Slope Restoration, Type B	4,000	SYD		
51	8210005	Monument Box, Adj	15	EA		
<b>TOTAL BID</b>						

Amount of Bid in Words

Respectfully submitted,

SEAL if BID is by a Corporation  
ATTEST:

Signature

Name of Contractor

Title

Address

GOURDIE-FRASER  
123 West Front Street  
Traverse City, Michigan 49684

Date: May 7, 2010

## ADDENDUM #2

PROJECT	BIDS DUE
Rosebush Drainage & Street Improvements GFA Project No: 09407	Date: May 12, 2010 Time: 10:00 am Location: Village of Rosebush 3901 North Mission Rd, Rosebush, MI 48878

This Addendum No. 2 is issued prior to the receipt of bid proposals to amend the Contract Documents and becomes part of the Contract Documents as of this date.

1. Use revised SPECIAL PROVISION FOR **ROADWAY GRADING** (SEE ATTACHED).
2. Add SPECIAL PROVISION FOR **ROADWAY GRADING (ALTERNATE)** (SEE ATTACHED). This Alternate has been added to the Bid Form.
3. Use revised PROGRESS CLAUSE (SEE ATTACHED)
4. 00400 BID FORM - USE THE ATTACHED BID FORM WHEN SUBMITTING YOUR BID - quantities have been changed & items have been added.
5. Plan set has been revised. Please go to:

<https://www.filesanywhere.com/FS/v.aspx?v=8971688c5d6670bd9c6e>

Click "Download" and "Save" the file to your computer before opening. It is a large file so saving it instead of opening it will save you time. If you click view/play you will not get the complete set of plans.

If you have any problems or need a paper set of these revised plans contact Vicky at Gourdie-Fraser, Inc. 231-946-5874.

This Addendum No. 2 supersedes the information in the originally issued Contract Documents, where applicable. The Contractor shall acknowledge receipt of any Addendums on the Bid Form included with his/her bid.

VILLAGE OF ROSEBUSH  
 SPECIAL PROVISION  
 FOR  
**ROADWAY GRADING**

GFA:BMB

1 of 1

05-6-10

**A. Description.** Remove miscellaneous structures and materials and complete all earthwork required to construct the proposed cross sections within the limits shown on the plans or stated in this special provision. All lines and grades will be as shown on the plans and/or as directed by the Engineer. Complete this work according to the MDOT 2003 Standard Specifications for Construction and this special provision.

**B. Materials.** Furnish and place additional material, conforming to the standard specifications for the type of work being completed, as necessary to achieve the typical cross sections. Use excavated material as embankment material, if suitable, as directed by the Engineer.

**C. Construction.** Complete this work according to applicable sections of the Standard Specifications for Construction. **Roadway Grading** includes, but is not limited to, the following work.

- Strip and stockpile topsoil for use in turf establishment.
- Furnish, place and compact additional suitable granular material.
- Clearing, including trees less than 6 inches in diameter.
- Remove rocks or boulders less than 0.5 cubic yards in volume.
- Removal of all other items which are identified as incidental and/or for which no other contract item applies.
- Remove, salvage, and replace existing signs, mailbox posts, bases, lamp posts, irrigation lines or heads, ornamental rocks, rock retaining walls, landscape timbers, and fences. If the owner does not want to keep the salvaged materials, then the Contractor assumes responsibility for the salvaged materials.
- Saw cutting existing pavement.
- Match drive and approach grades to new pavement grades.
- Remove miscellaneous structures and materials.
- Dispose of excess and unsuitable material according to section 205.
- **Provide 12" Minimum Class III Granular Subbase from ditch front slope to front slope, or minimum one foot behind curbs.**

**D. Measurement and Payment.** The completed work as measured will be paid for at the contract unit price for the following contract item (pay item).

<b>Contract Item (Pay Item)</b>	<b>Pay Unit</b>
Roadway Grading .....	Station

**Roadway Grading** will apply only where directed by the Engineer and will be measured along the construction centerline and shall include the entire grading limits on both sides of the road. Where a driveway or approach requires grading to meet proposed grades, this work is included in the measurement and payment for the item **Roadway Grading** in that area.

Turf establishment items will be paid for separately.

VILLAGE OF ROSEBUSH  
SPECIAL PROVISION  
FOR  
**ROADWAY GRADING (ALTERNATE)**

GFA:BMB

1 of 1

05-6-10

**A. Description.** Remove miscellaneous structures and materials and complete all earthwork required to construct the proposed cross sections within the limits shown on the plans or stated in this special provision. All lines and grades will be as shown on the plans and/or as directed by the Engineer. Complete this work according to the MDOT 2003 Standard Specifications for Construction and this special provision.

**B. Materials.** Furnish and place additional material, conforming to the standard specifications for the type of work being completed, as necessary to achieve the typical cross sections. Use excavated material as embankment material, if suitable, as directed by the Engineer.

**C. Construction.** Complete this work according to applicable sections of the Standard Specifications for Construction. **Roadway Grading** includes, but is not limited to, the following work.

- Strip and stockpile topsoil for use in turf establishment.
- Furnish, place and compact additional suitable granular material.
- Clearing, including trees less than 6 inches in diameter.
- Remove rocks or boulders less than 0.5 cubic yards in volume.
- Removal of all other items which are identified as incidental and/or for which no other contract item applies.
- Remove, salvage, and replace existing signs, mailbox posts, bases, lamp posts, irrigation lines or heads, ornamental rocks, rock retaining walls, landscape timbers, and fences. If the owner does not want to keep the salvaged materials, then the Contractor assumes responsibility for the salvaged materials.
- Saw cutting existing pavement.
- Match drive and approach grades to new pavement grades.
- Remove miscellaneous structures and materials.
- Dispose of excess and unsuitable material according to section 205.
- **Provide 12" Minimum Class II Granular Subbase from ditch front slope to front slope, or minimum one foot behind curbs.**

**D. Measurement and Payment.** The completed work as measured will be paid for at the contract unit price for the following contract item (pay item).

<b>Contract Item (Pay Item)</b>	<b>Pay Unit</b>
Roadway Grading .....	Station

**Roadway Grading** will apply only where directed by the Engineer and will be measured along the construction centerline and shall include the entire grading limits on both sides of the road. Where a driveway or approach requires grading to meet proposed grades, this work is included in the measurement and payment for the item **Roadway Grading** in that area.

Turf establishment items will be paid for separately.

**PROGRESS CLAUSE**

GFA:BMB

1 of 1

05-06-10

Start work in May 2010 or on the date designated as the starting date in the detailed Progress Schedule. In no case shall any work be commenced prior to receipt of formal Notice of Award by the Department.

The project shall be complete and ready for acceptance around August 31, 2010.

The low bidder for the work covered by this proposal will be required to attend a pre-construction meeting and present a detailed Progress Schedule. The schedule for this pre-construction meeting will be set within one week after the low bidder is determined. The Village of Rosebush and Project Engineer will arrange the time for the pre-construction meeting.

Named subcontractors for specialty and/or designated items, which materially affect the work schedule, shall also attend the pre-construction meeting and they will be required to sign the Progress Schedule to indicate their approval of the scheduled dates of work set forth in the Progress Schedule.

The Progress Schedule shall include, as a minimum, the controlling work items for the completion of the project and the planned dates that these work items will be controlling operations. The items of work as noted above and their anticipated completion dates shall also be noted in the Progress Schedule.

If the bidding proposal specifies other controlling dates, these shall also be included in the Progress Schedule.

**BID**

Proposal of \_\_\_\_\_  
(Hereinafter called "Bidder"), organized and existing under the Laws of the State of \_\_\_\_\_,  
doing business as \_\_\_\_\_,\* to \_\_\_\_\_

In compliance with your Request for Bids, Bidder hereby proposes to perform Work for the construction of Rosebush drainage and street improvements in strict accordance with the Contract Documents within the time set forth therein and at the prices stated below.

By submission of this Bid, each Bidder certifies, and in the case of a joint Bid, each party thereto certifies as to his own organization that this Bid has been arrived at independently, without consultation, communication, or agreement as to any matter relating to this Bid with any other Bidder or with any competitor.

Bidder hereby agrees to commence Work under this Contract on or before a date to be specified in the Notice to Proceed and to substantially complete the Project within 120 consecutive calendar days thereafter, and fully complete Project (including restoration, punch list items, maintenance bond, and close-out documents) within 30 days of Substantial Completion. Bidder further agrees to pay as liquidated damages, the sum of \$500.00 for each consecutive calendar day thereafter as provided in Section 00800 of the Supplemental General Conditions.

The Bidder hereby agrees to pay the actual cost for any construction observation, inspection, testing and project management time and expense for Engineering Services for work beyond the 60 work days. Bidder hereby agrees to also pay for the actual costs to the Owner for Resident Project Representative and Project management services and all additional inspection costs beyond the Contract completion date established by the "Notice to Proceed". (Reference – Section 00800 of the Supplemental Conditions.)

Bidder acknowledges receipt of the following Addendum:

\_\_\_\_\_  
\_\_\_\_\_

\*Insert "a Corporation", "a Partnership", or "an Individual" as applicable.

Bidder agrees to perform all work in the Contract Documents for the following prices:

	Pay Item	Description	Est. Quantity	Unit	Unit Price	Item Cost
1	1000001	Mobilization, Max. \$25,000	1	LS		
2	2020002	Tree, Rem, 19 inch to 36 inch	2	EA		
3	2020004	Tree, Rem, 6 inch to 18 inch	18	EA		
4	2030001	Culv, Rem, Less than 24 inch	23	EA		
5	2030011	Dr Structure, Rem	4	EA		
6	2030015	Sewer, Rem, Less than 24 inch	400	FT		
7	2040006	Curb and Gutter, Rem	173	FT		
8	2040011	Pavt, Rem	990	SYD		
9	2040013	Sidewalk, Rem	83	SYD		
10	2040030	Utility Pole, Rem	9	EA		
11	2050031	Roadway Grading	63	STA		
12	2050041	Subgrade Undercutting, Type II	1,200	CYD		
13	2080005	Erosion Control, Inlet Protection, Sediment Trap	45	EA		
14	2080025	Erosion Control, Silt Fence	1,000	FT		
15	2090001	Project Cleanup	1	LS		
16	3020001	Aggregate Base	5,500	TON		
17	3060015	Maintenance Gravel, LM	500	CYD		
18	3070025	Approach, CI II, 3 inch	1,611	SYD		
19	3070125	Shoulder, CI II, 3 inch	950	SYD		
20	4010860	Culv End Sect, Metal, 12 inch	47	EA		
21	4017001	Culv, CI A, 8 inch	855	FT		
22	4020005	Sewer, CI A, 15 inch, Tr Det A	310	FT		
23	4020033	Sewer, CI A, 12 inch, Tr Det B	1,500	FT		
24	4030005	Dr Structure, 48 inch dia	20	EA		
25	4030051	Dr Structure Cover	18,135	LB		
26	4030052	Dr Structure Cover, Adj, Case 1	8	EA		
27	4030053	Dr Structure Cover, Adj, Case 2	20	EA		
28	4030064	Dr Structure, Tap, 12 inch	3	EA		
29	5020034	HMA, 13A T	1,900	TON		
30	5020034	HMA, 13A L	850	TON		
31	5020125	HMA, 13A, 2 inch	150	SYD		
32	8010005	Driveway, Nonreinf Conc, 6 inch	100	SYD		
33	8020016	Curb and Gutter, Conc, Det B2	1,411	FT		
34	8020050	Driveway Opening, Conc, Det M	200	FT		

	Pay Item	Description	Est. Quantity	Unit	Unit Price	Item Cost
35	8030002	Sidewalk, Conc, 4 inch	1,300	SFT		
36	8030011	Sidewalk Ramp, ADA	600	SFT		
37	8100197	Sign, Type III, Erect, Salv	6	EA		
38	8120001	Barricade, Type III, High Intensity, Furn	2	EA		
39	8120002	Barricade, Type III, High Intensity, Oper	2	EA		
40	8120030	Flag Control	1	LS		
41	8120040	Lighted Arrow, Type B, Furn	2	EA		
42	8120041	Lighted Arrow, Type B, Oper	2	EA		
43	8120050	Minor Traf Devices	1	LS		
44	8120100	Plastic Drum, High Intensity, Furn	50	EA		
45	8120101	Plastic Drum, High Intensity, Oper	50	EA		
46	8120120	Sign, Type B, Temp, Furn	150	SFT		
47	8120121	Sign, Type B, Temp, Oper	150	SFT		
48	8130010	Riprap, Plain	50	SYD		
49	8140010	Paved Ditch, HMA	140	SYD		
50	8160051	Slope Restoration, Type A	4,000	SYD		
51	8160052	Slope Restoration, Type B	4,000	SYD		
52	8210005	Monument Box, Adj	15	EA		
<b>TOTAL BID</b>						

Alternate

53	2050031	Roadway Grading (Alternate)	63	STA		
----	---------	-----------------------------	----	-----	--	--

Amount of Bid in Words

Respectfully submitted,

SEAL if BID is by a Corporation  
ATTEST:

Signature

Name of Contractor

Title

Address